

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-053-20248-00-00  
Spot: SESWNE Sec/Twnshp/Rge: 21-14S-10W  
2310 feet from N Section Line, 1650 feet from E Section Line  
Lease Name: VOPAT D Well #: 12  
County: ELLSWORTH Total Vertical Depth: 2944 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2785		
PROD	4.5	2944		100 SX
SURF	8.625	266		165 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/24/2014 1:30 PM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: KEN BUEHLER Company: TRANS PACIFIC OIL CORP. Phone: (785) 483-1821

Proposed Plugging Method: AS PER KCC RULES & REGS

KCC WICHITA  
NR 2014  
RECEIVED

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE  
Date/Time Plugging Completed: 11/24/2014 4:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, TAG PREVIOUSLY SET CIBP AT 2785'. PERFORATE AT 1200', 900', 320'. RUN TUBING TO 2755' AND PUMP 100 SXS CEMENT. PULL TUBING TO 1200' AND PUMP 75 SX'S CEMENT TO SURFACE. PULL TUBING OUT AND CONNECTED ON TO 4.5" AND PUMPED 45 SX'S - DID CIRCUALTE CEMENT UP SURFACE CASING. TOPPED OFF WITH ANOTHER 20 SX'S CEMENT. USED A TOTAL OF 240 SX'S OF 60-40 POZ, 4% GEL.

Perfs:

Top	Bot	Thru	Comments
2828	2840	CSG	

Remarks: PERF TECH #12293. QUALITY CEMENT #886. WELL PLUGGED DUE TO 10 YEAR TA EXPIRATION.

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)  
12/11/14 ocm

*JK*