

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-053-20328-00-00
Spot: NENWNW Sec/Twnshp/Rge: 21-14S-10W
5025 feet from S Section Line, 4391 feet from E Section Line
Lease Name: VOPAT A Well #: 14
County: ELLSWORTH Total Vertical Depth: 2941 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	1800		
PROD	5.5	2938		225 SX
SURF	8.625	258		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/25/2014 10:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: KEN BUEHLER Company: TRANS PACIFIC OIL CORP. Phone: (785) 483-1821

Proposed Plugging Method: AS PER KCC RULES & REGS

KCC WICHITA
DEC 08 2014
RECEIVED

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 11/25/2014 1:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, TAG PREVIOUSLY SET CIBP AT 1800'. PERFORATE AT 1200', 900', AND 310'. RUN TUBING TO 1770' AND PUMP 100 SX'S CEMENT. PULL TUBING TO 1200' AND PUMP 55 SX'S - DID CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND CONNECT ON TO 5.5" AND PUMPED 60 SX'S CEMENT - DID CIRCULATE CEMENT UP SURFACE CASING. USED A TOTAL OF 215 SX'S.

Perfs:

Top	Bot	Thru	Comments
2842	2853	CSG	
2107	2112	CSG	

Remarks: 60/40 POZ, 4% GEL. PERF TECH #12294. QUALITY CEMENT #888. WELL PLUGGED DUE TO 10 YEAR TA EXPIRATION.

Plugged through: TBG

District: 02

Signed Virgil Clothier
12/11/14 cbm (TECHNICIAN)