

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-23942-00-00
Spot: NWSENESE Sec/Twnshp/Rge: 28-25S-15E
1960 feet from S Section Line, 640 feet from E Section Line
Lease Name: HARTZLER Well #: 43
County: WOODSON Total Vertical Depth: 1229 feet

Operator License No.: 33900
Op Name: LEIS, STEVEN A.
Address: 1135 30TH RD
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1229		150 SX
SURF	7	40		10 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 33900 Plug Co. Name: LEIS, STEVEN A.
Proposal Rcvd. from: STEVE LEIS Company: _____ Phone: (620) 330-6328

Proposed Plugging Method: 50ft at the bottom 50ft at the BK and cement from 250ft to surface

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 12/10/2014 1:15 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Operator hooked to casing, established flow, pump broke down and operator called Consolidated Oil Well Services to pump cement. Operator ran 1" pipe to TD, pumped 3sk portland, pulled pipe to top of KC pumped 3sk portland, pulled pipe to 250' circulated portland to surface, pulled pipe out, topped off with portland cement.

Perfs:

Top	Bot	Thru	Comments
1179	1189		

RECEIVED
DEC 18 2014
KCC Chanute Dist. #3
JA

Remarks:

Plugged through: CSG

District: 03

Signed John Almond
(TECHNICIAN)

KCC WICHITA

DEC 22 2014

RECEIVED

12/24/14 CKM