

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-24186-00-00
Spot: SENENWNE Sec/Twnshp/Rge: 6-32S-10W
337 feet from N Section Line, 1497 feet from E Section Line
Lease Name: DANA Well #: A1
County: BARBER Total Vertical Depth: 4803 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 124 N MAIN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4420		WITH 2 SX CMT
PC	5.5	2920		
PROD	5.5	4774	2275	WITH 150 SX CMT
SURF	8.625	250		WITH 225 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 12/08/2014 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SET CIBP @ 4420' WITH 2 SX CMT. SQUEEZED TOP PERFS WITH 30 SX CMT & 200# HULLS. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/08/2014 11:15 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4420' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. SQUEEZED PERFS AT 2836' WITH 200# HULLS & 30 SX CMT. TAG TOC @ 2700'. 1ST PLUG AT 590' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 305' WITH 50 SX CMT. 3RD PLUG AT 43' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4490	4526		
4470	4490		
2836	2854		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

12/24/14 CKM

District: 01

RECEIVED
DEC 11 2014
KCC DODGE CITY

Signed Stephen J. Pfeifer
(TECHNICIAN)
KCC WICHITA

DEC 19 2014
RECEIVED

SP