

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-21951-00-00
Spot: N2N2SE Sec/Twnshp/Rge: 23-24S-11W
2310 feet from S Section Line, 1320 feet from E Section Line
Lease Name: MCNICKLE Well #: 1
County: STAFFORD Total Vertical Depth: 4022 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3850		
PROD	5.5	4014	2105	WITH 150 SX CMT
SURF	8.625	256		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/04/2014 12:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SAND BOTTOM TO 3675' WITH 5 SX CMT. PLUG AT 540' WITH 10 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: PARTIAL
Date/Time Plugging Completed: 12/04/2014 4:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SANDED TO 3670' WITH 5 SX CMT. 1ST PLUG AT 545' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 270' WITH 120 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3726	3820		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

12/24/14 CKM

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
DEC 17 2014
KCC DODGE CITY

KCC WICHITA
DEC 19 2014
RECEIVED

[Signature]