

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-025-20796-00-00
Spot: S2S2N2NW Sec/Twnshp/Rge: 23-34S-25W
1000 feet from N Section Line, 1320 feet from W Section Line
Lease Name: THEIS Well #: B 1-23
County: CLARK Total Vertical Depth: 5900 feet

Operator License No.: 30233
Op Name: RED HILLS RESOURCES, INC.
Address: PO BOX 205
ENGLEWOOD, KS 67840

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5070		WITH 2 SX CMT
CIBP		5180		
CIBP		5714		
PROD 4.5		5900	2210	WITH 200 SX CMT
SURF 8.625		849		WITH 500 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/09/2014 10:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: MARLIN CLARK Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: SET CIBP @ 5070' WITH 2 SX CMT. PLUG AT 880' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40' TO SURFACE.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/09/2014 1:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 5070' WITH 2 SX CMT. 1ST PLUG AT 880' WITH 50 SX CMT. 2ND PLUG AT 300' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5657	5756		
5121	5127		

Remarks: USED CLASS A CEMENT BY SARGENT LILLARD.

Plugged through: CSG

12/24/14 CCM

District: 01

RECEIVED
DEC 11 2014
KCC DODGE CITY

Signed Larry Dickson PART II
KCC WICHITA (TECHNICIAN)
DEC 19 2014
RECEIVED