

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-001-31046-00-00  
Spot: NWSENENW Sec/Twnshp/Rge: 23-26S-18E  
900 feet from N Section Line, 2000 feet from W Section Line  
Lease Name: HARNER Well #: W-34  
County: ALLEN Total Vertical Depth: 870 feet

Operator License No.: 5491  
Op Name: W & W PRODUCTION COMPANY, GEN  
Address: 1150 HWY 39  
CHANUTE, KS 66720

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|------|------------|-------------|---------|
| SURF   | 7    | 21         |             |         |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/14/2014 12:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed  
Plugging  
Method:

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: NONE  
Date/Time Plugging Completed: 11/14/2014 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran 1" pipe to 862'. Pumped 3 sacks of gel & placed a 50' cement plug on bottom. Pulled 1" pipe to 500' & placed 14 sacks of portland cement at 500'. Pull 1" pipe to 250'. Pumped and circulated 58 sacks of portland cement to surface. Pulled the rest of the 1" pipe out of the hole and topped the well off with cement. A total of 3 sacks of gel and 86 sacks of portland cement was reported used to plug this well.

RECEIVED

DEC 02 2014

KCC Chanute Dist. #3

RD

Remarks:

Plugged through: TBG

District: 03

Signed \_\_\_\_\_

*[Signature]*  
12/24/14 CKM  
(TECHNICIAN)

KCC WICHITA

DEC 22 2014

RECEIVED