

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-10068-00-01
Spot: SWSWSW Sec/Twnshp/Rge: 8-31S-8W
382 feet from S Section Line, 4976 feet from E Section Line
Lease Name: DICKSON Well #: 2
County: HARPER Total Vertical Depth: 4525 feet

Operator License No.: 31337
Op Name: WILDCAT OIL & GAS LLC
Address: PO BOX 40
SPIVEY, KS 67142

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4524		250 SX
SURF	9.625	235		250 SX

Well Type: SWD UIC Docket No: E05673.1 Date/Time to Plug: 09/25/2014 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVE BRADY Company: QUALITY WELL SERVICE Phone: (620) 243-4401

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: PARTIAL
Date/Time Plugging Completed: 11/26/2014 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 4325' - CAPPED WITH 5 SXS CEMENT ON TOP. CUT CASING PIPE OFF @ 1550' PULLED 2 SHORT JOINTS OF CASING GOT STUCK, PUMPED 35 SXS CEMENT, DISPLACED TO 1250', LET SET OVER NIGHT, TAG TOC @ 820' CUT CASING OFF AGAIN @ 770' SPOTTED 35 SXS CEMENT. PULLED CASING TO 288' CIRCULATED TO SURFACE WITH 140 SXS CEMENT.

Perfs:

Top	Bot	Thru	Comments
4435	4445		

Remarks: ALL CEMENT WAS CLASS A COMMON. QUALITY WELL SERVICE SUPPLIED CEMENT FOR THIS JOB. TICKET #6275. FAILED MIT.

Plugged through: CSG

12/24/14 CKM

District: 02

Received
KANSAS CORPORATION COMMISSION

Signed B. J. Hope

cc:uic

(TECHNICIAN)

DEC 22 2014

CONSERVATION DIVISION
WICHITA, KS

✓