

051116

1-4

API NUMBER 15- 025-21,016 00190

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

NE NE NE, SEC. 18, T 30 S, R 24 W EX

4950 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033 JAN 6 1989

Operator: Murfin Drilling Company Base Name Bair Well # 1-18

Name & Address 250 North Water, Suite 300 County Clark 175.50

Wichita, KS 67202 Well Total Depth 5400 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1139

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Pickrell Drilling Company License Number 5123

Address 110 North Market, Suite 205, Wichita, KS 67202

Company to plug at: Hour: 2 a.m. Day: 4 Month: 1 Year: 1989

Plugging proposal received from Doyle Folkert

(company name) Pickrell Drilling Company (phone) 316-262-8427

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1550'

1st plug at 1550' with 40 sx cement, 2nd plug at 1160' with 50 sx cement,

3rd plug at 500' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:30 a.m. Day: 4 Month: 1 Year: 1989

ACTUAL PLUGGING REPORT 1st plug at 1550' with 40 sx cement,

2nd plug at 1160' with 50 sx cement,

3rd plug at 500' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)
I, XXX did not observe this plugging.

INVOICED

DATE 1-12-89

INV. NO. 23645

Signed Richard W. Lacey
(TECHNICIAN)

50

NOTICE OF INTENTION TO DRILL

*Corrected Card

(see rules on reverse side)

Expected Spud Date * 12-21-88 month day year

API Number 15- 025-21-016

OPERATOR: License # 6033
Name Murfin Drilling Company
Address 250 North Water, Suite 300
City/State/Zip Wichita, Ks. 67202
Contact Person * Scott Robinson
Phone 316-267-3241

Approx NE, NE, NE Sec. 18... Twp. 30S. S. Rg. 24... X West
.4950' Ft. from South Line of Section
* .330' Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet
County Clark

CONTRACTOR: License # 6033
Name Murfin Drilling Company - Pickrell
City/State Wichita, Ks. 67202

Lease Name BAIR Well # 1-18
Ground surface elevation 2538. est. feet MSL

Well Drilled For: Well Class: Type Equipment:
X Oil Storage Infield X Mud Rotary
Gas Inj X Pool Ext. Air Rotary
OWWO X Expl Wildcat Cable

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no

If OWWO: old well info as follows:

Depth to bottom of fresh water 200
Depth to bottom of usable water 500

Operator
Well Name
Comp Date Old Total Depth

Surface pipe by Alternate: 1 X 2
Surface pipe planned to be set 1100'

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Conductor pipe required na
Projected Total Depth 5450 feet

Date 12-13-88 Signature of Operator or Agent C. Scott Robinson

Formation MISS

For KCC Use:

Title Geological Manager

Conductor Pipe Required feet; Minimum Surface Pipe Required 520 feet per Alt. 1 R

This Authorization Expires 3-22-89 Approved By LRM 12-14-88 ORIG. REV'D: 9-22-88

SPUD DATE: 9-27-88
Spud 12-20-88

* WAS: 7000 AIRBENS 440' FEL

1100' of 8 5/8"

W.W. Yes.

RECEIVED STATE CORPORATION COMMISSION JAN 6 1989 CONSERVATION DIVISION Wichita, Kansas

PUSHER Doyle Folkert
TD 5400 FORMATION MISS
SURFACE PIPE 8 5/8 @ 1137
ANHYDRITE 1550 ELEVATION
STARTING TIME & DATE 2:00am 1-4-87
COMPLETION TIME & DATE 4:30am 1-4-89
1st PLUG @ 1550 FT. W/ 40 SX
2nd PLUG @ 1160 FT. W/ 50 SX
3rd PLUG @ 500 FT. W/ 40 SX
4th PLUG @ 40 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY Allied
TECHNICIAN Lacey
60/40 60%