

To: 1 051930
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-025-20,718
SW SE SE, SEC. 6, T 30 S, R 24 W/E

12-13

TECHNICIAN'S PLUGGING REPORT
Operator License # 30606

330 feet from S section line
990 feet from E section line
(Marathon)
Lease Name Huff A Well # 1

Operator: Murfin Drilling Co., Inc.
Name &
Address 250 N. Water, Ste. 300
Wichita, KS 67202

County Clark
Well Total Depth 5400 175.50 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 612

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage License Number 31529
Address: P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 1:30 p.m. Day: 13 Month: 12 Year: 19 95

Plugging proposal received from Richard McIntyre
(company name) Mike's Testing & Salvage (phone) 316-938-2943

work: 4 1/2" at 5398' w/250 sx cement, PBTD 5358', Perfs at 5266-72'
1st plug pump 2 sx hulls and 25 sx cement on bottom,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 13 Month: 12 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx common cement, displaced to 5000'

RECEIVED
KANSAS CORPORATION COMMISSION

2nd plug pumped down the 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.
Maximum pressure 600 psi and shut in 100 psi.

DEC 20 1995
12-20-95
CONSERVATION DIVISION
WICHITA, KS

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3200' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE JAN 09 1996
INV. NO. 44452

Signed Richard M. Lacey
(TECHNICIAN)

CP2/B
FORM CP-2/3
REV. 01-88