

To: 1 031257
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-22

API NUMBER 15-025-21,025 0000

SE SE NE, SEC. 7, T 30 S, R 24 W/NE
2970 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5123

Lease Name Oshlo Unit A Well # 4

Operator: Pickrell Drilling Company, Inc.
Name &
Address 110 N. Market, Ste. 205
Wichita, KS 67202

County Clark
Well Total Depth 5440 ^{176'} ₈₀ feet

Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 505

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524-0347

Company to plug at: Hour: 1 p.m. Day: 22 Month: 11 Year: 19 93

Plugging proposal received from Ed Mondero
(company name) Pickrell Drilling Company (phone) 913-798-2430

were: 4 1/2" at 5428', PBTD 5392', Perfs at 5270-74'
1st plug sand back to 5220' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 7 sx gel, 1 sx hulls, release 8 5/8" wiper
plug, and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1:50 p.m. Day: 22 Month: 11 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 5220' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 6 sx gel, 1 sx hulls, released 8 5/8"
wiper plug and pumped 150 sx cement.

Maximum pressure 100 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2600' of 4 1/2" casing
(if additional description is necessary, use BACK of this form)

INVOICED
I (did / ~~did not~~) observe this plugging.
DATE 12-8-93
INV. NO. 39424

RECEIVED
STATE CORPORATION COMMISSION
NOV 10 1993
CONSERVATION DIVISION
Wichita, Kansas
Signed Steve Durrant
(TECHNICIAN)