

1 090269

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-025-20,868 ~~8000~~ *R*

SE SW SW, SEC. 17, T. 30 S, R. 24 W
330 feet from W/S section line
4450 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 9657

Lease Name Pitman Well # 1-17
County Clark 177.13

Operator: Quintana Petroleum Corp.
Name & Address 818 17th Street, Suite 610
Denver, CO 80202

Well Total Depth 5450 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 814 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Aldebaran Drilling Co., Inc. License Number 5829
Address Box 18611, Wichita, KS 67207

Company to plug at: Hour: 9:00 pm Day: 22 Month: December Year: 19 84

Plugging proposal received from Tom Harmon

(company name) Aldebaran (phone) 316-685-5372

were: to fill hole with heavy mud and spot cement through drill pipe

- 1st plug at 1620' with 50 sx cement
- 2nd plug at 1050' with 70 sx cement
- solid bridge
- 3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement
- 5th plug to circulate rathole with 15 sx cement
- 6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Robert T. Tarbutton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:15 pm Day: 22 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1620' with 50 sx cement, 2nd plug at 1050' with 70 sx cement, 3rd & 4th plugs - solid bridge- hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun 11 AM 07 1985

(If additional description is necessary, use BACK of this CONSERVATION DIVISION
Wichita, Kansas

Signed R. T. Tarbutton
(TECHNICIAN)

INVOICED

DATE 1-15-85

INV. NO. 6437