

1 031256

11-23

APR NUMBER 15-025-20,794 <sup>AWB kcal</sup> 20807 - 0000

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

W/2 SW SW, SEC. 5, T 30 S, R 24 W/2  
660 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123  
Operator: Pickrell Drilling Company, Inc.  
Name:  
Address 110 N. Market, Ste. 205  
Wichita, KS 67202

Lease Name Oshlo Unit A Well # 3  
County Clark  
Well Total Depth 5442 <sup>176' 8"</sup> feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 514

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O.Box 347, Chase, KS 67524-0347

Company to plug at: Hour: 5 p.m. Day: 23 Month: 11 Year: 19 93

Plugging proposal received from Ed Mondero  
(company name) Pickrell Drilling Company, Inc. (phone) 913-938-2943

were: 4 1/2" at 5420' with 150 sx cement, PBTD 5379', Perfs at 5280-84'  
1st plug sand back to 5220' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 7 sx gel, 1 sx hulls, release 8 5/8" wiper  
plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 6:45 p.m. Day: 23 Month: 11 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 5220' and dumped 4 sx cement on top of sand through bailer,

2nd plug at 1240' with 50 sx cement,  
3rd plug at 540' with 50 sx cement,  
4th plug at 90' with 25 sx cement,  
5th plug topped off with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2800' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 30 1993  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

I (XXX) did not observe this plugging.

DATE 12-8-93  
INV. NO. 39423

Signed Steve Durrant (TECHNICIAN)