

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-24019-00-00
Spot: SWNENESW Sec/Twnshp/Rge: 30-15S-15W
2279 feet from S Section Line, 3024 feet from E Section Line
Lease Name: AR15 YARMER Well #: 1
County: RUSSELL Total Vertical Depth: 3472 feet

Operator License No.: 5039

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	958		400 sx

Op Name: AGV CORP.

Address: PO BOX 377 123 N MAIN
ATTICA, KS 67009

Well Type: DH

UIC Docket No:

Date/Time to Plug: 12/09/2014 12:00 AM

Plug Co. License No.: 34484

Plug Co. Name: FOSSIL DRILLING, INC.

Proposal Rcvd. from: CRAIG

Company: FOSSIL DRILLING, INC.

Phone: (620) 388-2676

Proposed Plugging Method: Ordered 240 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CHRIS NEELEY

WitnessType: NONE

Date/Time Plugging Completed: 12/09/2014 12:30 AM

KCC Agent: CHRIS NEELEY

Actual Plugging Report:

Perfs:

1st plug @3400 w/50 sx
2nd plug @1010 w/50 sx
3rd plug @400 w/100 sx
4th plug @40 w/10 sx

Rathole 30 sx

Remarks: ALLIED

Plugged through: DP

12/31/14 CKM

District: 04

Signed

Chris Neeley

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

DEC 11 2014

DEC 24 2014

CONSERVATION DIVISION
WICHITA, KS