

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-135-30251-00-00  
Spot: SWNESENE Sec/Twnshp/Rge: 26-19S-22W  
1888 feet from N Section Line, 536 feet from E Section Line  
Lease Name: ROBERT LENT Well #: 1  
County: NESS Total Vertical Depth: 4407 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>4058</u>	CIBP	5.5	1750	1420	WITH 2 SX CMT
Op Name: <u>AMERICAN WARRIOR, INC.</u>	PROD	5.5	4407	0	WITH 100 SX CMT
Address: <u>3118 CUMMINGS RD PO BOX 399</u> <u>GARDEN CITY, KS 67846</u>	SURF	8.625	1503		WITH 700 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/22/2014 9:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: SAND BOTTOM OFF AND 5 SX CMT. FIND CASING LEAKS AND PUT CIBP ABOVE THEM. PULL CASING AND PLUG WHILE PULLING.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/22/2014 1:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SANDED BOTTOM TO 4356' WITH 5 SX CMT. SET CIBP @ 1750' WITH 2 SX CMT. RUN LOG. DIDN'T FIND ANDY CEMENT TO SURFACE. SHOT CASING OFF AT 1550' & WOULDN'T COME LOOSE. PULLED ONE JOINT AND SPOTTED 50 SX CMT. PULLED TO 720' & SPOTTED 80 SX CMT. PULLED TO 320' & SPOTTED 50 SX CMT. PULLED CASING & TOPPED OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4390	4396		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

12/31/14 CKM

District: 01

RECEIVED  
DEC 23 2014  
KCC DODGE CITY

Signed Michael Maier  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

DEC 24 2014  
CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3