

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-145-21196-00-00  
Spot: S2S2SW Sec/Twnshp/Rge: 14-20S-20W  
481 feet from S Section Line, 4194 feet from E Section Line  
Lease Name: NEELAND Well #: 2  
County: PAWNEE Total Vertical Depth: 4350 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: 3118 CUMMINGS RD PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3250		WITH 2 SX CMT
PROD	5.5	4342	0	WITH 500 SX CMT
SURF	8.625	571		WITH 285 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/12/2014 10:30 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: SET CIBP ON BOTTOM WITH 2 SX CMT. PULL CASING IF POSSIBLE & PLUG ON WAY OUT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/12/2014 12:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 3250' WITH 2 SX CMT. COULDN'T GET BELOW 3250' BECAUSE THERE WAS SOMETHING IN THE HOLE. RUN BOND LOG. DIDN'T FIND ANY CMT. RUN TBG & PACKER. FOUND HOLE IN CASING AT 1400'. PUMP ON CASING. IT CIRCULATED TO SURFACE ON BACKSIDE. PUMPED 400 SX CMT AND IT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4248	4265		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL SWIFT SERVICES.

Plugged through: CSG

12/31/14 CKM

District: 01

Signed Michael Maier  
(TECHNICIAN)

RECEIVED  
DEC 22 2014  
KCC DODGE CITY

Received  
KANSAS CORPORATION COMMISSION  
DEC 24 2014  
CONSERVATION DIVISION  
WICHITA, KS