

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-145-21197-00-00
Spot: W2W2SW Sec/Twnshp/Rge: 14-20S-20W
1328 feet from S Section Line, 4929 feet from E Section Line
Lease Name: NEELAND Well #: 3
County: PAWNEE Total Vertical Depth: 4300 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4110		WITH 2 SX CMT
PROD	5.5	4299	0	WITH 500 SX CMT
SURF	8.625	537		WITH 275 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/12/2014 10:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Revd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: SET CIBP ON BOTTOM WITH 2 SX CMT. PULL CASING IF POSSIBLE & PLUG ON WAY OUT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/12/2014 12:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4110' WITH 2 SX CMT. RUN BOND LOG & FOUND CEMENT AT 700' TO 1700'. PERFORATED AT 600' & PUMPED 160 SX CMT. CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4243	4353		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

12/31/14 ckm

District: 01

RECEIVED
DEC 22 2014
KCC DODGE CITY

Signed Michael Maier

(TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION
DEC 24 2014
CONSERVATION DIVISION
WICHITA, KS