

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-00493-00-01
Spot: SWNWSE Sec/Twnshp/Rge: 22-14S-16W
1685 feet from S Section Line, 2374 feet from E Section Line
Lease Name: THOLEN Well #: 1
County: ELLIS Total Vertical Depth: 3409 feet

Operator License No.: 4787
Op Name: TDI
Address: 1310 BISON RD
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3369		100sx
SURF	8.625	218		125 SX
T1	2.375	2830		

Well Type: EOR UIC Docket No: E28737.1 Date/Time to Plug: 12/04/2014 9:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JEFF CRAWFORD Company: T D I Phone: (785) 650-9879

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 500 # hulls and 8 sx gel.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/04/2014 3:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3150' and pumped 8 sx gel followed by 75 sx cement w/150 # hulls. Pulled tubing to 1600' and pumped 100 sx cement w/200 # hulls. Well started to circulate at the end of displacement. Pulled tubing to 400' and WOC. Ran tubing to 537' and pumped 75 sx cement w/50 # hulls. Cement circulated. POOH. Filled casing w/10 sx cement and shut in. Hooked to braden head and pumped 20 sx cement at 300 psi. Shut in.

GPS: 38.81752 -099.08533

Perfs:

Top	Bot	Thru	Comments
3331	3334		
3320			
3298	3302		
3279	3283		
3267	3271		
3258	3262		
3200	3202		
3194	3196		
3187	3190		
3144	3146		
3118	3302		
3023	3027		
2869	3027		

Remarks: GLOBEL CEMENTING TICKET # 1546

Plugged through: TBG

12/17/14 OPM

District: 04

Signed Ray A. Dinkel
cc: uic (TECHNICIAN) CM

KCC WICHITA

DEC 16 2014

RECEIVED

DEC 11 2014