

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-21634-00-00  
Spot: NWSWSE Sec/Twnshp/Rge: 21-14S-16W  
1024 feet from S Section Line, 2361 feet from E Section Line  
Lease Name: LANG Well #: 3  
County: ELLIS Total Vertical Depth: 3410 feet

Operator License No.: 4787  
Op Name: TDI  
Address: 1310 BISON RD  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3395		150 SX
SURF	8.625	213		145 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/03/2014 9:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: JEFF CRAWFORD Company: TDI Phone: (785) 871-7311

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 500 # hulls and 7 sx gel.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/04/2014 4:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3300' and pumped 6 sx gel followed by 50 sx cement w/50 # hulls. Pulled tubing to 1638' and pumped 150 sx cement w/125 # hulls. Cement circulated late. POOH. Cement down 560' (13-14 seconds down) Filled casing w/40 sx cement. WOC. Cement 2 seconds down. Topped off. Hooked to braden head and pumped 10 sx cement at 500 psi. Shut in. Checked fill up late that day. Cement down 4-5 seconds (200').  
12/04/2014- Topped off w/15 sx mixed cement.  
  
GPS: 38.81569 -099.10374

Perfs:

Top	Bot	Thru	Comments
3361	3393		
3120	3296		

Remarks: GLOBEL CEMENTING TICKET # 1543

Plugged through: TBG

*12/17/14 CKM*

District: 04

Signed Ray A Dinkel  
(TECHNICIAN) *CKM*

KCC WICHITA

DEC 16 2014

RECEIVED

DEC 11 2014