

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-115-19110-00-02
Spot: NWSWNE Sec/Twnshp/Rge: 18-21S-3E
3630 feet from S Section Line, 2310 feet from E Section Line
Lease Name: GOOD B Well #: B-5
County: MARION Total Vertical Depth: 3230 feet

Operator License No.: 5399
Op Name: TREK AEC, LLC
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2818		300 SX
SURF	8.625	110		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/19/2014 8:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: LUKE KOEHN Company: SUNFLOWER WELL SERVICE Phone: (620) 755-3089

Proposed Plugging Method: As per Kansas Corporation Commission's recommendations, in accordance with their rules and regulations, as per their instructions.

Plugging Proposal Received By: HUNTER CLARK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/20/2014 2:00 PM KCC Agent: HUNTER CLARK

Actual Plugging Report:

RIGGED UP RAN TUBING DOWN TO 1734' HIT A HARD BRIDGE DOWN HOLE. RIGGED UP A SWIVEL AND WASHED DOWN TO THE DEPTH OF 2732' CIRCULATE HOLE CLEAN THEN SET A 35 SXS HOT PLUG 60/40 4% 3% CC. TRIPPED OUT AND WASHED UP. RETURNED 11/20 RUN DOWN TO 250' WITH 2" AND CIRCULATE CEMENT TO SURFACE WITH 40 SXS. THEN RAN 1" DOWN TO 250' ON THE BACKSIDE AND PUMPED ANOTHER 50 SXS TO FILL UP THE SURFACE. PULLED BOTH STRINGS HOLE STAYED FULL, NO TOP OFF NEEDED.

Perfs:

Top	Bot	Thru	Comments
2818	2822		
2815	2821		

Remarks: CEMENT TICKET #48486 11/19 #48476 11/20 CONSOLIDATED

Plugged through:

District: 02

Signed [Signature] 12/17/14 CKM
(TECHNICIAN)

KCC WICHITA

Form CP-2/3

DEC 12 2014

RECEIVED

✓ SK