

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-075-20781-00-01  
Spot: SWNWSESE Sec/Twnshp/Rge: 34-22S-43W  
844 feet from S Section Line, 1025 feet from E Section Line  
Lease Name: BLAND CATTLE CO B Well #: 1-34 OWWO  
County: HAMILTON Total Vertical Depth: 5350 feet

Operator License No.: 5822  
Op Name: VAL ENERGY, INC.  
Address: 125 N MARKET ST STE 1710  
WICHITA, KS 67202

| String | Size  | Depth (ft) | Pulled (ft) | Comments        |
|--------|-------|------------|-------------|-----------------|
| CIBP   |       | 4742       |             | WITH 5 SX CMT   |
| DVT    |       | 1951       |             | WITH 245 SX CMT |
| PROD   | 5.5   | 5156       | 0           | WITH 200 SX CMT |
| SURF   | 8.625 | 1219       |             | WITH 250 SX CMT |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/08/2014 12:00 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: JAVIER Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/08/2014 4:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4742' WITH 5 SX CMT. PLUG AT 1980' WITH 30 SX CMT. PUMP 120 SX CMT FROM 1225' TO 0'. FULL CIRCULATION. TOP OFF 5 1/2" CASING WITH 10 SX CMT. PUMP 20 SX CMT DOWN THE ANNULUS. PRESSURE TO 300#.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 4814 | 4840 |      |          |
| 4792 | 4804 |      |          |

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED  
DEC 10 2014  
KCC DODGE CITY

Signed

Ken Jehlik  
KCC WICHITA (TECHNICIAN)

DEC 12 2014  
RECEIVED

12/17/14 ckm