

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-03134-00-02
Spot: SENENE Sec/Twnshp/Rge: 9-10S-24W
4367 feet from S Section Line, 496 feet from E Section Line
Lease Name: BELL Well #: 4
County: GRAHAM Total Vertical Depth: 4055 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| L1 | 4.5 | 3998 | | 110 sx |
| PROD | 5.5 | 4053 | | 150 SX |
| SURF | 8.625 | 184 | | 160 SX |

Well Type: EOR UIC Docket No: E21432.1 Date/Time to Plug: 12/01/2014 2:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JOEL STULL Company: ALLIED CEMENT COMPANY Phone: (785) 885-8240

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 14 sx gel and 400 # hulls.
DV Tool at 2088' w/560 sx cement.
Perforations: 3791' - 4004'.

Plugging Proposal Received By: PAT BEDORE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/01/2014 3:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied on to casing and pumped 70 sx cement, followed by 11 sx gel, followed by 150 sx cement. Shut in pressure 1000 psi. Tied on to backside and squeezed w/15 sx cement. Shut in pressure 2100 psi.

GPS: 39.20192 -099.99767

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4000 | 4004 | | |
| 3980 | 3988 | | |
| 3962 | 3966 | | |
| 3848 | 3852 | | |
| 3791 | 3794 | | |

Remarks: ALLIED CEMENT TICKET # 055602

Plugged through: CSG

District: 04

Signed

CC-UIC
KCC WICHITA

(TECHNICIAN)

12/17/14 CKM

DEC 08 2014

DEC 16 2014

RECEIVED