

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-03135-00-00
Spot: NWNENE Sec/Twnshp/Rge: 9-10S-24W
330 feet from N Section Line, 990 feet from E Section Line
Lease Name: BELL Well #: 2
County: GRAHAM Total Vertical Depth: 4083 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4083		700 SX
SURF	8.625	200		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/01/2014 10:00 AM
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE
Proposal Rcvd. from: JOEL STULL Company: SMOKY HILLS WELL SERVICE Phone: (785) 885-8240

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 10 sx gel and 500 # hulls.
Perforations: 4007' - 4010'.
5 1/2" cemented w/700 sx cement.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/01/2014 1:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3999' and pumped 10 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 2542' and pumped 150 sx cement w/200 # hulls. Pulled tubing to 1116' and pumped 250 sx cement w/150 # hulls. Good circulation of cement. Pulled tubing. Topped off w/35 sx cement full. Tied on to backside and squeezed w/15 sx cement. Shut in pressure 200 psi.
GPS: 39.20358 -099.99997

Perfs:

Top	Bot	Thru	Comments
4007	4010		

Remarks: ALLIED CEMENT TICKET # 55550

Plugged through: TBG

District: 04

Signed

[Signature]

(TECHNICIAN)

KCC WICHITA

CM

DEC 16 2014

RECEIVED

DEC 08 2014

12/17/14 ckm