

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-20946-00-00
Spot: SWNESE Sec/Twnshp/Rge: 32-16S-29W
1679 feet from S Section Line, 1034 feet from E Section Line
Lease Name: MADRID Well #: 32-9
County: LANE Total Vertical Depth: 4560 feet

Operator License No.: 5011
Op Name: VIKING RESOURCES, INC
Address: 400 N WOODLAWN ST, STE 18
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2252	0	WITH 520 SX CMT
SURF	8.625	299		WITH 200 SX CMT

Well Type: SWD UIC Docket No: D23480.0 Date/Time to Plug: 11/26/2014 10:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: MIKE FRITZLER Company: WHITETAIL CRUDE Phone: (785) 798-3641

Proposed Plugging Method: RUN TBG TO BOTTOM & PUMP HULLS & CMT UNTIL CMT CIRCULATES IN 4 1/2". PULL TBG & TOP OFF. CHECK BACKSIDE WITH 50 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/26/2014 3:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 1800' & PUMPED 110 SX CMT & 300# HULLS. CMT CIRCULATED.
PULLED TBG & TOPPED OFF WITH 25 SX CMT. TIED ONTO BACKSIDE &
PRESSURED TO 500# & HELD. COULDN'T PUMP ANY CMT.

Perfs:

Top	Bot	Thru	Comments
1910	1920		
1895	1905		
1875	1890		
1845	1860		
1810	1835		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier
CC: UIC (TECHNICIAN)

RECEIVED

DEC - 5 2014

KCC DODGE CITY

KCC WICHITA

DEC 12 2014

RECEIVED

Form CP-2/3