

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-22283-00-00
Spot: SWSWSENW Sec/Twnshp/Rge: 20-29S-15W
2577 feet from N Section Line, 1313 feet from W Section Line
Lease Name: THOMPSON Well #: 2-20
County: PRATT Total Vertical Depth: 4912 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 155 N MARKET STE 700
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4900	2608	WITH 165 SX CMT
SURF	8.625	412		WITH 400 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/18/2014 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SAND BACK TO 4618' WITH 5 SX CMT. PLUG AT 950' WITH 50 SX CMT. PLUG AT 450' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL
Date/Time Plugging Completed: 11/18/2014 2:30 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SANDED BACK TO 4618' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 965' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 440' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4694	4714		

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: CSG

District: 01

RECEIVED
DEC - 5 2014
KCC DODGE CITY

Signed

Robert Dila

(TECHNICIAN)

KCC WICHITA

DEC 12 2014

RECEIVED

12/17/14 CCM

SR