

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-115-21437-01-00
Spot: NENENWNE **Sec/Twnshp/Rge:** 30-19S-2E
254 feet from N Section Line, 1376 feet from E Section Line
Lease Name: JOST **Well #:** 2-30H
County: MARION **Total Vertical Depth:** 3866 feet

Operator License No.: 34692
Op Name: ZENERGY OPERATING COMPANY, LL
Address: 6100 S YALE AVE, STE 1700
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3800		
I1	7	3144		500 sx cement
PROD	7	3144		500 SX
PROD	4.5	5456		340 SX
SURF	9.625	235		150 SX
T1	2.875	1904		

Well Type: OIL **UIC Docket No:** **Date/Time to Plug:** 11/05/2014 12:00 AM
Plug Co. License No.: 5893 **Plug Co. Name:** PRATT WELL SERVICE, INC.
Proposal Rcvd. from: STEVE HELM **Company:** PRATT WELL SERVICE **Phone:**

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: **WitnessType:** COMPLETE (100%)
Date/Time Plugging Completed: 11/06/2014 12:00 AM **KCC Agent:** HUNTER CLARK

Actual Plugging Report:

RAN DOWN TO 2841' AND SPOTTED 150 SXS CLASS A 4% C.C. TAGGED @ 2260'.
 RAN DOWN TO 315' WITH TUBING AND CIRC 80 SXS CLASS A 2% GEL 1.5% C.C.
 100 LBS HULLS. CEMENT DID CIRCULATE TO SURFACE. CHECK TOP PLUG ON
 11/14/14 CEMENT STILL @ SURFACE.

Perfs:

Top	Bot	Thru	Comments
4908	5140		
4658	4908		
4270	4658		
3813	4028		
3590	3813		
3144	5456		

Remarks: CEMENT TICKET #42976 COPLAND
Plugged through: TBG

KCC WICHITA
DEC 12 2014
RECEIVED
 12/17/14 CKM

District: 02 **Signed** [Signature] **(TECHNICIAN)**