

To: 1 090674  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-151-20,673-00-00  
200' W of  
S/2 S/2 N/2 SEC. 14, T 27 S, R 15 W/X

TECHNICIAN'S PLUGGING REPORT

4-29

Operator License # 9408

Lease Name Newby Well # 1-14

Operator: Trans Pacific Oil Corporation

County Pratt 155.67

Name  
Address 100 N. Main, Ste. 1000  
Wichita, KS 67202

Well Total Depth 4790 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 336

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor D S & W Well Servicing Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525-0231

Company to plug at: Hour: 11:30 a.m. Day: 29 Month: 4 Year: 1996

Plugging proposal received from Kent Strube

(company name) D S & W Well Servicing Inc. (phone) 316-587-3361

logs: 4 1/2" at 4715' w/150 sx cement, PBTB 4464', Perfs at 4430-34'

1st plug sand back to 4375' and dump 4 sx cement on top of sand through bailer.

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement. 04-31-96

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:30 p.m. Day: 29 Month: 4 Year: 1996

ACTUAL PLUGGING REPORT 1st plug sanded back to 4375' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pump 100 sx cement. Maximum pressure 300 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2280' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
Please observe this plugging.

DATE MAY 06 1996

INV. NO. 45531

Signed (TECHNICIAN)