

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-20616-00-00
Spot: NWSENE Sec/Twnshp/Rge: 14-21S-40W
3930 feet from S Section Line, 1250 feet from E Section Line
Lease Name: FRACK Well #: 2-14
County: HAMILTON Total Vertical Depth: 2805 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2804	0	WITH 700 SX CMT
SURF	8.625	352		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/11/2014 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 200# HULLS & 180 SX CMT. PRESSURE TO 500#. CHECK ANNULUS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/11/2014 12:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:


FILL 4 1/2" CASING WITH CMT FROM 2782' TO 0' USING 150 SX CMT & 200# HULLS. PRESSURE TO 1500#. HOLDING. PUMP 15 SX CMT DOWN ANNULUS TO 200#. HOLDING.

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

12/24/14 *cm*

RECEIVED
DEC 17 2014
KCC DODGE CITY

KCC WICHITA
DEC 19 2014
RECEIVED

