

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-20622-00-00
Spot: SW Sec/Twnshp/Rge: 26-22S-40W
1238 feet from S Section Line, 4062 feet from E. Section Line
Lease Name: HOWELL Well #: 2-26
County: HAMILTON Total Vertical Depth: 2725 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| PROD | 4.5 | 2724 | 0 | WITH 550 SX CMT |
| SURF | 8.625 | 347 | | WITH 225 SX CMT |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/11/2014 1:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed
Plugging
Method:

FILL 4 1/2" CASING WITH 250# HULLS & 175 SX CMT. PRESSURE TO 50#. CHECK ANNULUS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/11/2014 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH CMT FROM 2698' TO 0' USING 195 SX CMT AND 200# HULLS. PRESSURE TO 500#. HOLDING. PUMP 15 SX CMT DOWN THE ANNULUS TO 200#. HOLDING. TOP OFF 4 1/2" CASING WITH 5 SX CMT.

Perfs:


| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2688 | 2698 | | |

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

12/24/14 CKM

RECEIVED
DEC 17 2014
KCC DODGE CITY

KCC WICHITA
DEC 19 2014
RECEIVED

Form CP-2/3