

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-075-20697-00-00  
Spot: N2SESW Sec/Twnshp/Rge: 11-23S-41W  
1261 feet from S Section Line, 3307 feet from E Section Line  
Lease Name: THUROW Well #: 2-11  
County: HAMILTON Total Vertical Depth: 2630 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, LLC  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2630	0	WITH 475 SX CMT
SURF	8.625	810		WITH 225 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/11/2014 1:00 PM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: FILL 4 1/2" CASING WITH 250# HULLS & 170 SX CMT. PRESSURE TO 500#. CHECK ANNULUS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/11/2014 4:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH CMT FROM 2571' TO 0' USING 195 SX CMT & 250# HULLS. PRESSURE TO 500#. HOLDING. PUMP 20 SX CMT DOWN THE ANNULUS TO 200#. HOLDING. TOP OFF 4 1/2" CASING WITH 5 SX CMT.

Perfs:


Top	Bot	Thru	Comments
2566	2571		
2556	2561		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

12/24/14 CKM

RECEIVED

DEC 17 2014

KCC DODGE CITY

KCC WICHITA

DEC 19 2014

RECEIVED

Form CP-2/3