

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-21082-00-01
Spot: NENE Sec/Twnshp/Rge: 18-29S-20W
660 feet from N Section Line, 660 feet from E Section Line
Lease Name: MCDERMET SWD Well #: 1
County: KIOWA Total Vertical Depth: 6659 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5830		WITH 2 SX CMT
PROD	5.5	5895	2759	WITH 190 SX CMT
SURF	8.625	600		WITH 225 SX CMT

Well Type: SWD UIC Docket No: D30440.0 Date/Time to Plug: 12/08/2014 1:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BUD NEFF Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: SET CIBP @ 5830' WITH 2 SX CMT. PLUG AT 1350' WITH 20 SX GEL & 50 SX CMT. PLUG AT 630' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE
Date/Time Plugging Completed: 12/08/2014 1:40 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5830' WITH 2 SX CMT. 1ST PLUG AT 1352' WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 628' WITH 50 SX CMT. 3RD PLUG AT 62' WITH 30 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5880	6659		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

K/M. [Signature] 12/24/14 oxm
cc: uic (TECHNICIAN)

RECEIVED

DEC 17 2014

KCC DODGE CITY

KCC WICHITA

DEC 19 2014

RECEIVED