

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19211-00-01
Spot: SESWSE Sec/Twnshp/Rge: 28-27S-6E
164 feet from S Section Line, 1732 feet from E Section Line
Lease Name: STERNS-MORRIS Well #: 1
County: BUTLER Total Vertical Depth: 3079 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 1117 N.W. 24TH ST.
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3054		
PROD	5.5	3054		255 SX
SURF	13	850		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/22/2014 8:00 AM
Plug Co. License No.: 34928 Plug Co. Name: IRON HORSE WELL SERVICE LLC
Proposal Rcvd. from: DALLAS FLOWERS Company: CROWN ENERGY COMPANY Phone: (316) 323-3869

Proposed Plugging Method: AS PER KCC RULES & REGS/ CIBP @ 3000' W/2 SXS / CIRC. 250'-0' AFTER DIGGING WELL OUT.

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 10/23/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG CIRCUALTED VARIOUS BRIDGES FROM 30'-1397', OUTSIDE CASING @ 1397'. W/TBG @ 1390', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 35 SXS CLASS A COMMON 3% CC & DISPLACED IN CASING. WAITED 2 HRS, TAGGED CEMENT PLUG @ 980'. RIH ON WIRELINE, SHOT SQUEEZE HOLES @ 250'-251' (4 HOLES). RIH W/ TBG @ 260', CONSOLIDATED OIL WELL ESTABLISHED CIRCULATION, MIXED & PUMPED 215 SXS 60/40 POZMIX 4% GEL 3% CC. CEMENT DID NOT CIRCULATE. 10-23-2014, TAGGED CEMENT 47' INSIDE CASING, 37' OUTSIDE CASING & 26' ON BACKSIDE. RIH W/ 1" TBG ON BACKSIDE @ 26', & 37' OUTSIDE 5 1/2", & 47' INSIDE 5 1/2" CASING CEMENTING ALL THREE STRINGS & CIRCUALTED 50 SXS 60/40 POZMIX 4% GEL 3% CC TO SURFACE. CEMENT CIRCUALTED. PLUG DOWN 11:00 AM 10-23-2014.

Perfs:

Top	Bot	Thru	Comments
3054	3079	CSG	

Remarks: CONSOLIDATED CEMENTING TICKET #46538 & 46539.

Plugged through: TBG

12/24/14 ckm

District: 02

Received
KANSAS CORPORATION COMMISSION

DUANE KRUEGER

(TECHNICIAN)

DEC 22 2014

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

JK