

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-119-20824-00-01
Spot: SWNE Sec/Twnshp/Rge: 17-34S-28W
3213 feet from S Section Line, 2087 feet from E Section Line
Lease Name: ROSS Well #: 3-17
County: MEADE Total Vertical Depth: 6500 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
30129	CIBP		5170		WITH 2 SX CMT
Op Name: <u>EAGLE CREEK CORPORATION</u>	CIBP		5730		WITH 2 SX CMT
Address: <u>8100 E. 22ND ST. NORTH, BLDG 1500 S</u>	PROD	5.5	6026	2500	WITH 325 SX CMT
<u>WICHITA, KS 67226</u>	SURF	8.625	1628		WITH 650 SX CMT

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/11/2014 9:30 AM

Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION

Proposal Rcvd. from: Company: Phone:

Proposed Plugging Method: Set Wireline Bridge Plug at 5730. Set Wireline Bridge Plug at 5170. Dump bail two sacks of cement on top of bridge plug at 5170. Shoot off and pull 5.5" casing. Through tubing, spot 20 sacks gel in front of 50 sacks cement at 1650'. Cement 40 sacks at 500'. Cement 20 sacks from 60' to Ground level.

Plugging Proposal Received By: ERIC MACLAREN
Date/Time Plugging Completed: 12/11/2014 12:00 PM

Witness Type: COMPLETE (100%)
KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP'S AT 5730' & 5170' WITH 2 SX CMT ON TOP. 1ST PLUG AT 1650' WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 500' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 60 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5782	5790		
5292	5298		
5222	5235		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

12/24/14 OKM

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED

DEC 17 2014

KCC DODGE CITY

KCC WICHITA

DEC 19 2014

RECEIVED

Form CP-2/3