

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-151-10212-00-01  
Spot: NWNWSE Sec/Twnshp/Rge: 7-27S-12W  
2330 feet from S Section Line, 2359 feet from E Section Line  
Lease Name: ICHU Well #: 24  
County: PRATT Total Vertical Depth: 4245 feet

Operator License No.: 31739  
Op Name: IUKA-CARMI DEVELOPMENT LLC  
Address: PO BOX 847  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	4331		TOP OF LINER IS 4111'
PROD	5.5	4216	0	WITH 200 SX CMT
SURF	8.625	452		WITH 200 SX CMT

Well Type: SWD UIC Docket No: D14493.0 Date/Time to Plug: 11/24/2014 1:00 PM  
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.  
Proposal Rcvd. from: GARELD INSLEE Company: IUKA-CARMI DEVELOPMENT Phone: (620) 672-9571

Proposed Plugging Method: RUN TBG TO 620' & CIRCULATE CMT TO SURFACE. PUMP 30 SX CMT DOWN BACKSIDE IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/24/2014 3:00 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

**\*\*STUCK IN HOLE: BIT, BIT SUB, 118.2' OF 3 1/2" DRILL COLLARS, & 20' OF 2 7/8" TBG.\*\*** RUN TBG TO 620'. CIRCULATE CMT TO SURFACE INSIDE 5 1/2" CASING WITH 100 SX CMT. CHECK BACKSIDE. PUMP DOWN BACKSIDE WITH 7 SX CMT. PRESSURE TO 250#. TOP OFF 5 1/2" WITH 3 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4331	4429	OH	

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

12/24/14 CKM

District: 01

Signed [Signature] (TECHNICIAN)

RECEIVED  
DEC 11 2014  
KCC DODGE CITY

KCC WICHITA  
DEC 19 2014  
RECEIVED

[Signature]  
Form CP-2/3