

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-019-40504-00-00  
Spot: NENENENW Sec/Twnshp/Rge: 6-34S-12E  
5096 feet from S Section Line, 2855 feet from E Section Line  
Lease Name: PERU FARM Well #: 12  
County: CHAUTAUQUA Total Vertical Depth: 1135 feet

Operator License No.: 32255  
Op Name: KANSAS ENERGY COMPANY, L.L.C.  
Address: BOX 68  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.25	975		0 SX
SURF	10	12		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/01/2014 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Revd. from: P.J. BUCK Company: \_\_\_\_\_ Phone: (620) 725-3636

Proposed Plugging Method: Surface and production cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull out and perforate at 700' and 350'. Run 1" back in and spot 50' of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL  
Date/Time Plugging Completed: 10/02/2014 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report: Ran 1" to 860' gelled hole and spotted 20 sack plug. Pulled 1" and perforated casing at 650' and 350'. Ran back into 650' and spotted 20 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 152 sacks of cement were used to plug this well.

Perfs: \_\_\_\_\_  
RECEIVED  
DEC 17 2014  
KCC Chanute Dist. #3  
DS

Remarks: WELL WAS PLUGGED DUE TO PLUGGING AGREEMENT SIGNED BY OPERATOR.  
Plugged through: TBG

District: 03 Signed [Signature] (TECHNICIAN)  
12/24/14 CKM

Received  
KANSAS CORPORATION COMMISSION  
DEC 19 2014  
CONSERVATION DIVISION  
WICHITA, KS