

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-22973-00-00
Spot: NESWSWE Sec/Twnshp/Rge: 3-10S-24W
570 feet from S Section Line, 2220 feet from E Section Line
Lease Name: RAY Well #: 1
County: GRAHAM Total Vertical Depth: 4080 feet

Operator License No.: 30076
Op Name: ANDERSON, ANDY (DECEASED) DBA
Address: PO BOX 100
HILL CITY, KS 67642

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4078		175 SX
SURF	8.875	210		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/24/2014 11:00 AM
Plug Co. License No.: 33612 Plug Co. Name: GEIST, RON DBA WILDCAT WELL SERVICE
Proposal Rcvd. from: RON GEIST Company: GEIST, RON DBA WILDCAT WELL Phone: (785) 728-2040

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 4% gel cement, 6 sx gel and 500 # hulls.
Production perforations: 3826' - 4052'.
Port Collar at 2132' w/425 sx cement.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/24/2014 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 4 1/2" casing and pumped 75 sx cement w/300 # hulls followed by 6 sx gel spacer followed by 175 sx cement. Maximum pressure 500 psi. Shut in pressure 500 psi. Hooked to 8 5/8" x 4 1/2" annulus and pumped 25 sx cement. Shut in pressure 100 psi.

GPS: 39.20600N -099.98572W

Perfs:

Top	Bot	Thru	Comments
4018	4024		
3982	3985		

Remarks: GLOBAL CEMENTING TICKET # 1541

Plugged through: CSG

12/31/14 CFM

District: 04

Signed _____

Pat Bedore
RECEIVED (TECHNICIAN)
KANSAS CORPORATION COMMISSION

CM

DEC 09 2014

DEC 24 2014
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3