

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-22974-00-00
Spot: NWNENWSE Sec/Twnshp/Rge: 2-8S-24W
2570 feet from S Section Line, 1780 feet from E Section Line
Lease Name: ANDERSON Well #: 1
County: GRAHAM Total Vertical Depth: 3850 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>30076</u>	<u>CIBP</u>		<u>3675</u>		
Op Name: <u>ANDERSON, ANDY (DECEASED) DBA</u>	<u>PROD</u>	<u>4.875</u>	<u>3847</u>		<u>175 SX</u>
Address: <u>PO BOX 100</u>	<u>SURF</u>	<u>8.875</u>	<u>209</u>		<u>150 SX</u>
<u>HILL CITY, KS 67642</u>					

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/24/2014 10:00 AM
Plug Co. License No.: 33612 Plug Co. Name: GEIST, RON DBA WILDCAT WELL SERVICE
Proposal Rcvd. from: RON GEIST Company: GEIST, RON DBA WILDCAT WELL Phone: (785) 728-2046

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix 4% gel cement, 6 sx gel and 300 # hulls.
Production perforations: 3638' - 3685'.
Port Collar at 1992' w/290 sx cement.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/24/2014 10:45 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

8 5/8" x 4 1/2" annulus visually checked and there is cement to surface. Hooked to 4 1/2" casing and pumped 50 sx cement w/200 # hulls followed by 6 sx cement gel spacer, followed by 200 sx cement. Maximum pressure 500 psi. Shut in pressure 300 psi.

GPS: 39.38547N -099.96362W

Perfs:

Top	Bot	Thru	Comments
3794	3797		
3770			
3741	3744		
3683	3686		
3675			
3638	3640		

Remarks: GLOBAL CEMENTING TICKET # 1540

Plugged through: CSG

12/31/14 CKM

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

DEC 09 2014

DEC 24 2014

CONSERVATION DIVISION
WICHITA, KS