

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-30334-00-00  
Spot: NWNWSW Sec/Twnshp/Rge: 17-15S-17W  
2310 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: LEIKER B Well #: 1  
County: ELLIS Total Vertical Depth: 3570 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3569		250 SX
SURF	8.625	1138		485 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/19/2014 9:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: GRESSEL OILFIELD SERVICE, LLC Phone: (316) 524-1225

Proposed Plugging Method: Ordered 530 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Packer stuck at 3131'. Top of fish at 2666' (2 7/8") tubing.  
KC open hole  
Arb plug at 3490' CIBP  
Alt I completion

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/19/2014 2:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Gressel perforated at 1100'. Ran in hole with tubing to 2630'. Copeland rigged to tubing and mixed and pumped 60 sx neat cement followed by 65 sx cement w/200 # hulls mixed in. Pulled tubing to 1650'. Copeland rigged to tubing and pumped 405 sx cement w/250 # hulls mixed in to circulate cement up 8 5/8" casing and 4 1/2" casing. Pulled tubing. Ran out of cement. Will top off on Monday, 12/22/2014.  
12/22/2014- Topped off well with 25 sx cement. Hole standing full. Ticket # 42125

GPS: 38.74674 -099.24449  
2304' FSL 4956' FEL  
SW NW NW SW

Perfs:

Top	Bot	Thru	Comments
3240	3442		

Remarks: GRESSEL OILFIELD CEMENTING CO TICKET # 42209

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*[Signature]*  
(TECHNICIAN)

12/31/14 CKM

KCC WICHITA

CM

DEC 30 2014

Form CP-2/3

RECEIVED

DEC 22 2014