

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-22759-00-00
Spot: NENESW Sec/Twnshp/Rge: 9-22S-12W
2287 feet from S Section Line, 2995 feet from E Section Line
Lease Name: BRENSING Well #: 1
County: STAFFORD Total Vertical Depth: 3825 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3249		
PROD	5.5	3823	0	WITH 185 SX CMT
SURF	8.625	252		WITH 160 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/12/2014 12:00 PM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: RUN TBG TO 881' & CIRCULATED CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/12/2014 2:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

CASING LEAKS AT 650' TO 1018' WERE SQUEEZED WITH 250 SX CMT, CIRCULATING CMT TO SURFACE. 12/12/14: COULD ONLY GET TBG DOWN TO 680' DUE TO COLLAPSED CASING. CIRCULATED CMT TO SURFACE WITH 80 SX CMT. PULLED TBG & TOPPED OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3670	3678		
3334	3692		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: TBG

12/31/14 CKM

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
DEC 22 2014
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

DEC 24 2014
CONSERVATION DIVISION
WICHITA, KS