

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-24108-00-00
Spot: SWNWNSW Sec/Twnshp/Rge: 22-33S-8E
2172 feet from S Section Line, 3667 feet from E Section Line
Lease Name: MONTGOMERY Well #: 8
County: CHAUTAUQUA Total Vertical Depth: 2306 feet

Operator License No.: 32557
Op Name: BLUESTEM, INC
Address: 1226 W COUNTY LINE RD
CEDAR VALE, KS 67024

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2306		75 SX
SURF	8.625	522		275 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/10/2014 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: FLOYD MONTGOMERY Company: _____ Phone: (620) 758-2809

Proposed Plugging Method: 10 sks cement bottom plug, gel the hole, 5 sks cement middle plug about 1200' 550 to surface top plug

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL
Date/Time Plugging Completed: 11/10/2014 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 2250' gelled hole and spotted 13 sack plug. Pulled 1" and perforated casing at 1000' and 550'. Ran 1" back into 1000' and spotted 7 sacks of cement. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 165 sacks of cement were used to plug this well.

Perfs:

RECEIVED
DEC 23 2014
KCC Chanute Dist. #3

DS

Remarks:

Plugged through: TBG

12/31/14 ccm

District: 03

Signed Duane A Sims
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

DEC 29 2014
CONSERVATION DIVISION
WICHITA, KS