

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-26289-00-01
Spot: SESWNESE Sec/Twnshp/Rge: 29-33S-16E
1485 feet from S Section Line, 910 feet from E Section Line
Lease Name: MAYO Well #: 1
County: MONTGOMERY Total Vertical Depth: 1428 feet

Operator License No.: 34027
Op Name: CEP MID-CONTINENT LLC
Address: PO BOX 970
SKIATOOK, OK 74070

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		850		
PROD	4.5	1197		110 SX
SURF		43		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/05/2014 12:00 AM
Plug Co. License No.: 3097 Plug Co. Name: K W OIL WELL SERVICE, INC.
Proposal Rcvd. from: TODD BAKER Company: _____ Phone: (918) 214-2737

Proposed Plugging Method: RUN TUBING TO BOTTOM OF WELL. FILL FROM BOTTOM TO SURFACE WITH CEMENT.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 11/06/2014 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

Pulled equipment and well was perfed at 300', 500' and 900'. Ran 1" to 1075' and hit. Pumped 11 bbls of cement. Pulled out 1" to 500'. Circulated cement to surface with 1/2 bbl. Pulled 1" to 200' and circulated cement to surface with 1/2 bbl. Pulled all of 1" and topped off with 1/2 bbl.

Perfs:

Top	Bot	Thru	Comments
822	826		

RECEIVED
DEC 23 2014
KCC Chanute, KS 3
RH

Remarks:

Plugged through: TBG

District: 03

Signed Russell Hine
(TECHNICIAN)

12/31/14 CKM

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

DEC 29 2014

CONSERVATION DIVISION
WICHITA, KS