

TO: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-097-21657-01-00
 Spot: S2NENENE Sec/Twnshp/Rge: 18-29S-20W
330 feet from N Section Line, 185 feet from E Section Line
 Lease Name: STEWART Well #: 1-H
 County: KIOWA Total Vertical Depth: 5172 feet

Operator License No.: 32334
 Op Name: CHESAPEAKE OPERATING, LLC
 Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	7.625	4002		WITH 4 SX CMT
CIBP		5780		WITH 50 SX CMT
CIBP		6145		
CIBP		6565		
CIBP		7000		
CIBP		7320		
CIBP		7620		
CIBP		8000		
CIBP		8250		
L1	7.625	5810	2380	TOC @ 3764'
PROD	5.5	8376	4000	WITH 155 SX CMT
SURF	10.75	809		WITH 760 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/17/2014 3:00 PM
 Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
 Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
 Date/Time Plugging Completed: 12/17/2014 7:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:
 SET CIBP @ 5780' WITH 50 SX CMT. RECOVERED 4000' OF 5 1/2". SET TBG PACKER AT 3950' & PUMPED 300 SX CMT WITH 300# HULLS, 3% CC. WENT ON VACUUM. SET 7 5/8" CIBP AT 4002' WITH 4 SX CMT. RECOVERED 2380' OF 7 5/8". 1ST PLUG AT 1411' WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 859' WITH 100 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CMT CIRCULATED.

Total MD = 8746'
 Per ACO1

RECEIVED
 DEC 22 2014

Received
 KANSAS CORPORATION COMMISSION
 DEC 24 2014
 CONSERVATION DIVISION
 WICHITA, KS

KCC DODGE CITY

Perfs:

Top	Bot	Thru	Comments
8205	8207		
8144	8146		
8120	8122		
8090	8092		
8036	8038		
7934	7936		
7894	7896		
7836	7838		
7740	7742		
7708	7710		
7674	7676		
7570	7572		
7516	7518		
7490	7492		
7440	7442		
7410	7412		
7380	7382		
7280	7282		
7240	7242		
7166	7168		
7134	7136		
7099	7101		

7064	7066
6936	6938
6874	6876
6812	6814
6768	6770
6726	6728
6682	6684
6440	6442
6356	6358
6302	6304
6254	6256
6222	6224
6170	6172
6120	6122
6096	6098
6042	6044
6000	6002
5945	5947
5848	5850


Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

12/31/14 CCM

District: 01

Signed



(TECHNICIAN)

Form CP-2/3



RECEIVED
 DEC 22 2014
 KCC DODGE CITY



Received
 KANSAS CORPORATION COMMISSION
 DEC 24 2014
 CONSERVATION DIVISION
 WICHITA, KS