

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-25037-00-00
Spot: N2SENV Sec/Twnshp/Rge: 1-17S-22W
1648 feet from N Section Line, 2011 feet from W Section Line
Lease Name: BARBER "B" Well #: 1-1
County: NESS Total Vertical Depth: 4335 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 1019
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT	5.5	1576		WITH 150 SX CMT
PROD	5.5	4334	0	WITH 150 SX CMT
SURF	8.625	221		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/11/2014 1:00 PM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: BRIAN KARLIN Company: DOWNING NELSON Phone: (785) 623-3290

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 50 SX CMT & 150# HULLS. PULL TBG TO 1600' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/11/2014 3:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4330' & SPOT 50 SX CMT & 250# HULLS. PULL TBG TO 1600' & PUMP 160 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 30 SX CMT. TIED ONTO BACKSIDE & PRESSURED TO 300# RIGHT AWAY.

Perfs:

Top	Bot	Thru	Comments
4331	4335		
4325	4331		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: TBG

12/31/14 ckm

District: 01

Signed *Michael Maier*
(TECHNICIAN)

RECEIVED
DEC 22 2014
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION
DEC 24 2014
CONSERVATION DIVISION
WICHITA, KS