

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-06998-00-01
Spot: SWNENW Sec/Twnshp/Rge: 20-19S-14W
990 feet from N Section Line, 1650 feet from W Section Line
Lease Name: ZIMMER Well #: A-1
County: BARTON Total Vertical Depth: 2447 feet

Operator License No.: 7383
Op Name: GRADY BOLDING CORPORATION
Address: 114 NORTH MAIN P.O. BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2362		300 SX
SURF	8.625	824		400 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/16/2014 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: GRADY BOLDING Company: GRADY BOLDING CORPORATION Phone: (620) 564-2240

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/11/2014 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped off w/5 sx cement. Cut casing at 1404'. Tied to casing and pumped 100 sx cement w/200 # hulls. Cut casing at 900' and pumped 50 sx cement w/100 # hulls. Pulled casing to 450'. Circulated cement to surface w/120 sx cement and 200 # hulls. Pulled casing. Hole stayed full.

GPS: 38.38802 -098.89767

Perfs:

Top	Bot	Thru	Comments
2252	2258		
1850	1850		
1784	1787		
1772	1780		
1760	1768		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

12/31/14 CRM

DEC 22 2014

KCC WICHITA

Form CP-2/3

DEC 30 2014

RECEIVED