

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-24702-00-00  
Spot: E2SE Sec/Twnshp/Rge: 20-19S-14W  
1320 feet from S Section Line, 660 feet from E Section Line  
Lease Name: LEROY Well #: 1  
County: BARTON Total Vertical Depth: 3580 feet

Operator License No.: 7383  
Op Name: GRADY BOLDING CORPORATION  
Address: 114 NORTH MAIN P.O. BOX 486  
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3574		150 SX
SURF	8.625	817		400 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/11/2014 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: GRADY BOLDIN Company: GRADY BOLDING CORPORATION Phone: (620) 564-2240

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/11/2014 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped off w/5 sx cement. Holes in casing at 1404'. Tied to casing and pumped 40 sx cement. Cut casing at 780' and pumped 100 sx cement. Pulled casing to 380'. Circulated cement to surface w/115 sx cement. Pulled casing and topped off w/50 sx cement.

GPS: 38.79860 -098.88715

Perfs:

Top	Bot	Thru	Comments
3497	3502		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed

Bruce Rodie  
(TECHNICIAN)

12/31/14 CRM

CM

DEC 22 2014

KCC WICHITA Form CP-2/3

DEC 30 2014

RECEIVED