

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-25839-00-00
Spot: NESENWSE Sec/Twnshp/Rge: 4-17S-24W
1813 feet from S Section Line, 1639 feet from E Section Line
Lease Name: STEVE Well #: 1-4
County: NESS Total Vertical Depth: 4660 feet

Operator License No.: 9855
Op Name: GRAND MESA OPERATING COMPANY
Address: 1700 N WATERFRONT PKWY BLDG 600
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	221		WITH 150 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/16/2014 10:45 PM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: RICH WHEELER Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1830' WITH 50 SX CMT. 2ND PLUG AT 1050' WITH 80 SX CMT. 3RD PLUG AT 500' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: LARRY HARRIS Witness Type: NONE
Date/Time Plugging Completed: 12/17/2014 12:45 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

Perfs:

1ST PLUG AT 1830' WITH 50 SX CMT. 2ND PLUG AT 1050' WITH 80 SX CMT. 3RD PLUG AT 500' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

12/31/14 CKM

District: 01

RECEIVED

DEC 22 2014

KCC DODGE CITY

Signed

[Signature]

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

DEC 24 2014

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3