

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-06014-00-00  
Spot: E2E2NENW Sec/Twnshp/Rge: 33-11S-19W  
660 feet from N Section Line, 2560 feet from W Section Line  
Lease Name: SOLOMON Well #: 7  
County: ELLIS Total Vertical Depth: 3652 feet

Operator License No.: 5010  
Op Name: KNIGHTON OIL COMPANY, INC.  
Address: 1700 N WATERFRONT PKY BLDG 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	2.5	3530		0 SX
PROD	5.5	3646		0 SX
SURF	10.63	195		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/04/2014 10:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: KEN WERNER Company: KNIGHTON OIL Phone: (785) 623-4081

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 4% gel cement w/300 # hulls.  
Tubing cemented in.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/04/2014 2:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran 1" tubing to 3307' and pumped 20 sx cement. Pulled 1" tubing to 2257' and pumped 20 sx cement. Pulled 1" tubing to 1207' and pumped 25 sx cement to circulate cement to surface. Pulled all 1" tubing and topped off 2 1/2" tubing w/5 sx cement. Hooked to 10 3/4" x 5 1/2" annulus and pumped 55 sx cement. Shut in pressure 150 psi.

GPS: 39.05754N -099.43605W

Perfs:

Top	Bot	Thru	Comments
3646	3652		

Remarks: CONSOLIDATED TICKET # 47876

Plugged through: TBG

*12/21/14 CKM*

District: 04

Signed \_\_\_\_\_

*Pat Bedore*

(TECHNICIAN)  
Received  
KANSAS CORPORATION COMMISSION

CM

DEC 19 2014

DEC 24 2014

Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS