

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-20672-00-00
Spot: NESWNE Sec/Twnshp/Rge: 27-12S-21W
3630 feet from S Section Line, 1650 feet from E Section Line
Lease Name: KING EDITH Well #: 5
County: TREGO Total Vertical Depth: 3959 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>5010</u>	PROD	5.5	3959		825 SX
Op Name: <u>KNIGHTON OIL COMPANY, INC.</u>	SURF	8.625	603		365 SX
Address: <u>1700 N WATERFRONT PKY BLDG 100</u> <u>WICHITA, KS 67206</u>					

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/17/2014 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: KEN WERNER Company: EXPRESS WELL SERVICE & SUPPL Phone: (785) 623-4081

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforations at 3295' - 3925'.
DV Tool at 1648' w/500 sx cement.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/17/2014 12:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3751' and pumped 10 sx gel followed by 120 sx cement w/300 # hulls. Pulled tubing to 1875' and pumped 250 sx cement. Good circulation of cement. Pulled tubing out. Topped off casing w/50 sx cement full. Tied on to backside and it was full. No cement needed.

GPS: 38.98193 -09963721

Perfs:


Top	Bot	Thru	Comments
3295	3925		

Remarks: QUALITY OILWELL CEMENTING TICKET # 1066

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

12/31/14 CKM

KCC WICHITA Form CP-2/3

DEC 30 2014

RECEIVED

DEC 22 2014