

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-20673-00-00
Spot: NWNENE Sec/Twnshp/Rge: 27-12S-21W
4950 feet from S Section Line, 990 feet from E Section Line
Lease Name: KING EDITH Well #: 6
County: TREGO Total Vertical Depth: 3900 feet

Operator License No.: 5010
Op Name: KNIGHTON OIL COMPANY, INC.
Address: 1700 N WATERFRONT PKY BLDG 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3900		725 SX
SURF	8.625	612		365 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/16/2014 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: KEN WERNER Company: EXPRESS WELL SERVICE & SUPPL Phone: (785) 623-4081

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement, 11 sx gel and 500 # hulls.
DV Tool at 1648' w/450 sx cement.
Perforations: 3533' - 3854'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: NONE
Date/Time Plugging Completed: 12/16/2014 12:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3751' and pumped 10 sx gel followed by 110 sx cement w/250 # hulls. Pulled tubing to 1750' and pumped 190 sx cement. Good circulation of cement. Pulled tubing and topped off w/30 sx cement full. Tied on to back side and squeezed w/ 0 sx cement. Well full. Shut in 150 psi.

GPS: 38.98555 -099.63482

Perfs:

Top	Bot	Thru	Comments
3533	3854		

Remarks: QUALITY CEMENT TICKET # 1064

Plugged through: TBG

District: 04

Signed _____

[Signature]
12/21/14 CKM
(TECHNICIAN) CM

Received
KANSAS CORPORATION COMMISSION

DEC 16 2014

DEC 24 2014

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3