

State of Kansas



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

AUG. 13 1962
 08-13-62
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date 8 -7, 1962, authorized the following plugging operation:

Operator's full Name: Rex & Morris And Kenneth Rupp

Complete Address: Box 334 El Dorado Kan.

Lease Name: Gemeinhardt Well No. #1

Location: W/2 - W/2/ SE 1/4 Sec. 28 Twp. 27 Rge. 13 (E) (W)

County: Pratt Total Depth: 4550

Oil Well Gas Well Input Well SWD Well

D & A Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

351' of 8 5/8" Surface pipe circulated with cement. Hole filled
to 300' with heavy drilling mud ~~1st~~ 1/4 sack hulls 1st
cemting plug 20 sacks cement through drill pipe. Hole
filled to 35' with heavy drilling mud 1/4 sack hulls & 10
sacks cement to bottom of cellar. Rat hole bridged 2 sacks
cement

Very truly yours,

Herman Gustus

